

Supply & Install Agreement — Fort Frances & Area Wireless Broadband Network

Between: Jam21.net ("the Customer") **and:** Northern Wireless Inc. ("NWI" / "the Supplier") **Date:** July 17, 2026 **Reference:** NWI-CTR-FF-2026 · Rev 0 **Relates to:** NWI Proposal NWI-PROP-FF-2026 (issued July 3, 2026)

1. Purpose

NWI shall engineer, supply, install, commission and test a complete fixed-wireless broadband network for the Customer serving Fort Frances and the surrounding area, as described in the Proposal and detailed in the Schedule of Supply & Pricing (Section 8).

2. Scope of Supply

NWI's turnkey scope comprises:

- Engineering and administration (site study, design, drawings, technical manual, procurement).
- Tower supply, installation, power and lighting.
- Tower POP (head-end) equipment and installation.
- Wireless backhaul equipment and installation.
- Core wired network (bandwidth control, switch, primary/secondary servers, T1/router hand-off).
- Premise equipment for **100 initial subscriber connections**.
- Commissioning and testing.

The network is designed for **60 Mbps** capacity across up to **8 break-out locations**.

3. Customer Responsibilities

The Customer is responsible for: tower rental; IP address allocation; purchase and resale of bandwidth; traffic and usage data collection; subscriber firewalls; per-POP battery backup; and providing timely approvals of tower sites, network design and procurement orders. NWI provides power conditioning and outage protection on backbone equipment and recommended spares.

4. Ownership & Handover

On completion of commissioning and testing and receipt of final payment, title to all supplied equipment passes to the Customer, who thereafter owns and operates the network. NWI provides operator training and vendor documentation (hard and soft copy).

5. Schedule & Milestones

Milestone	Target date
Contract execution & kickoff	July 20, 2026
Site study, design & drawings approved	August 21, 2026

Milestone	Target date
Procurement complete	September 18, 2026
Tower, POP & backbone installed	October 16, 2026
Last-mile & premise equipment installed	November 13, 2026
Commissioning, testing & handover	December 4, 2026

Dates are confirmed in the project master schedule, agreed by both parties before execution. Time is of the essence.

6. Contract Price

The total firm price for the supply and install scope is **CAD \$97,500**, exclusive of applicable taxes, per the Schedule of Supply & Pricing in Section 8.

7. Payment Milestones

#	Milestone	%	Amount (CAD)
1	Contract execution & kickoff	30%	\$29,250
2	Procurement complete	30%	\$29,250
3	Installation complete	30%	\$29,250
4	Commissioning, testing & handover	10%	\$9,750
Total		100%	\$97,500

Invoices are due net 15 days from milestone completion.

8. Schedule of Supply & Pricing

All amounts in Canadian dollars, exclusive of applicable taxes.

8.1 Engineering & Admin

Item	Unit	Qty	Unit Price	Total
Site visit (2 days)	Each	1	\$1,640	\$1,640
Site study	Days	5	\$520	\$2,600
Site layout drawing	Days	2	\$520	\$1,040
Network design and drawing	Days	3	\$520	\$1,560
Technical manual	Days	5	\$520	\$2,600
Procurement time	Days	2	\$520	\$1,040
Subtotal				\$10,480

8.2 Tower

Item	Unit	Qty	Unit Price	Total
Tower supply	Each	1	\$13,000	\$13,000
Tower installation	Each	1	\$2,500	\$2,500
Tower power and lighting	Each	1	\$1,500	\$1,500
Subtotal				\$17,000

8.3 Tower POP (Head-End)

Item	Unit	Qty	Unit Price	Total
Antennas	Each	1	\$800	\$800
Amplifiers	Each	1	\$1,000	\$1,000
AP in a box	Each	1	\$3,000	\$3,000
Cabling and connectors	Each	1	\$200	\$200
Installation of above	Each	1	\$500	\$500
Subtotal				\$5,500

8.4 Wireless Backhaul

Item	Unit	Qty	Unit Price	Total
Antenna units	Each	1	\$4,600	\$4,600
Cabling and connectors	Each	1	\$300	\$300
Installation both ends	Each	1	\$600	\$600
Subtotal				\$5,500

8.5 Core Wired Network

Item	Unit	Qty	Unit Price	Total
Bandwidth control unit	Each	1	\$4,000	\$4,000
Main hub / switch	Each	1	\$400	\$400
Primary server	Each	1	\$5,000	\$5,000
Secondary server	Each	1	\$5,000	\$5,000
T1 / router installation	Each	1	\$2,500	\$2,500
Server / network installation	Each	1	\$2,600	\$2,600
Subtotal				\$19,500

8.6 Premise Equipment (100 Subscribers)

Item	Unit	Qty	Unit Price	Total
Radio	Each	100	\$220	\$22,000
Antenna	Each	100	\$60	\$6,000
Cable	Each	100	\$12	\$1,200
Connectors	Each	200	\$10	\$2,000
Subtotal				\$31,200

8.7 Commissioning

Item	Unit	Qty	Unit Price	Total
On-the-ground testing	Days	6	\$520	\$3,120
Installed on-site testing	Days	10	\$520	\$5,200
Subtotal				\$8,320

8.8 Total

Section	Total (CAD)
Engineering & Admin	\$10,480
Tower	\$17,000
Tower POP (Head-End)	\$5,500
Wireless Backhaul	\$5,500
Core Wired Network	\$19,500
Premise Equipment	\$31,200
Commissioning	\$8,320
Total Supply & Install	\$97,500

9. Warranty & Support

NWI passes through manufacturer warranties on all supplied equipment and warrants its installation workmanship for **12 months** from handover. Recommended spares (power supplies, antennas, radios, connectors, cable) are supplied. Remote monitoring is standard on all wireless products in this design.

10. Changes

Any change to scope, quantities or pricing is handled by written change order signed by both parties before the affected work proceeds.

11. General

Each party is responsible for its own obligations under this Agreement. Matters not addressed here — including insurance, liability limits, dispute resolution and governing law — are to be settled between the parties' representatives prior to execution. This is a mock agreement prepared for illustration and is not a binding legal instrument.

12. Acceptance

Accepted and agreed:

For Jam21.net Name: _____ Title: _____ Date: _____ Signature: _____

For Northern Wireless Inc. Name: Jim Cox Title: Project Manager Date: _____ Signature: _____

Northern Wireless Inc. — turnkey wireless internet solutions. Figures are illustrative for planning purposes.